

480

(7) Estimate for the probable quantities for constructing a shop.

No.	Items of work	Per	Quantity
1	Earthwork excavating foundation	100 c. ft.	841
2	Burnt brick in mortar		1,144
3	Do mud		1,232
4	Burnt stone slabs 6" thick dressed	8. ft.	147
5	Plastering with chunam	100 s. ft.	2,795
6	White and colourwashing		2,795
7	Teakwood doors complete panelled	S. ft.	74
8	Do big doors with plank for shops		56
9	Do windows complete		48
10	Teakwood wrought and put up with oiling	C. ft.	53'00
11	Roofing with 1st class Mangalore tiles over teak reepers.	100 s. ft.	695
12	Ridge tiles set in mortar	R. ft.	29
13	Roofing with terrace complete	100 s. ft.	185
14	Brick masonry parapet wall including plastering and top cornice.	R. ft.	37
15	Cornice		40
16	Chunam borders		32
17	Teakwood eave board with painting		25
18	Chocolate painting, 2 coats	100 s. ft.	332
19	Levelling the ground and clearing site	Lump	sum

(8) Estimate for the probable quantities for adding a verandah in front of the Quarter Guard and Prison.

No.	Items of work	Per	Quantity
1	Dismantling and remaining the existing parapet	S. ft.	83
2	Preparing stone brackets and inserting in the walls	No.	4
3	Teakwood wrought and put up	C. ft.	50'00
4	Roofing with Mangalore tiles over teak reepers	100 s. ft.	300
5	Ridge tiles set in mortar	R. ft.	14
6	Teakwood 1" plank		72
7	Zinc sheet 2" wide		72
8	Teakwood eave board with painting		60
9	Do barged board with finials	No.	2
10	Do railings with painting	R. ft.	40
11	Removing and refixing doors and windows with masonry and plastering between the pillars of verandah.	No.	3
12	Chocolate painting	Lump	sum

K. V. KARVE,
Assistant Engineer.

HASSAN DIVISION.

Abstract Notification dated 2nd May 1920:

The attention of the public is invited to pages 293 and 294 of the *Mysore Gazette*, dated 13th May 1920, calling for tenders for executing the remaining works of "Improving the Hindlanahalli tank, Channarayapatna Taluk, Hassan District."

B. C. SRINIVASA LYRNGAR,
Executive Engineer.